CAPA Asphalt & Airport Pavement Meeting

9:30am, Thursday March 12, 2020

Rocky Mountain Regional Airport (Mt. Evans Room)

AGENDA

9:30 am Welcome and Introductions (*Tom Peterson*, CAPA)

1. Rocky Mountain Metropolitan Airport Overview (Host Facility)
Paul Anslow, Airport Director
Brian Bishop, Operations Manager

2. Colorado Airport Operators Association Update
Ken Lawson, Business Director

3. CDOT Aeronautics Program Update
Scott Storie, Program Manager
Kip McClain, Program Manager
Dave Ulane, Director

4. **2020 FAA Denver ADO CO & WY Update**
Funding Update / Grant & Project Approvals / Notice to Proceed
Marc Miller, Denver Airports District Office

5. FAA Specifications and Technical Updates
Jake Hoban, Garver
AC 150/5370-10H Standards for Specifying Construction of Airport

- - - - - - - - BREAK - - - - - - - -

6. **Report Card on Colorado Aviation Infrastructure**
Steve Hakes, Benesch
Bill Epp, Benesch

7. 2020 Industry Outlook – Liquid Asphalt Binder
John Wilkins, Suncor Energy

8. **"Best in Colorado" Award – Meadow Lake Airport Case Study**
Jeremy Packer, Jviation

11:45 Lunch Provided: Sponsor Presentation
Drew Vance & Dan Stephens

vancebrothers
Bringing Integrity to the Surface.

Northwest Mountain Region

Denver Airports District Office

2020

Airport	Consultant	Project	Estimated Bid Schedule	Estimated Quantity
Larger Projects				
Colorado Springs, CO	RS&H	Rehabilitate Runway	March 24, 2020 (Construction in 2021)	76,525
Kremmling	Armstrong	Rehabilitate Runway (re-bid)	April 2020	10,000
Rifle, CO		Expand Apron	June, 2020	8,500
Pinedale, WY	T-O	Construct Apron & Rehabilitate Runway	Fall 2020 for 2021 Construction	23,000
Rawlins, WY	T-O	Rehabilitate Runway	March 26, 2020	12,000
				130,025
Smaller Projects				
Canon City, CO	Armstrong	Rehabilitate Taxiway (and sealcoat), Reconstruct a portion of the Runway	March 18, 2020	1,070
Durango, CO	Dibble	Rehabilitate Portion of Air Carrier Ramp	May 21, 2020	1,600
Holyoke, CO	Armstrong	Airfield Pavement Maintenance	April 2020	80,000 SY (P-608)
La Junta, CO	Dibble	Rehabilitate Taxiway and Apron	May 28, 2020	350
Limon, CO	Armstrong	Construct Taxilane	April 2020	500 (P-403)
Salida, CO	Dibble	Rehabilitate Taxiway	May 29, 2020	250
Evanston, WY	T-O	Rehabilitate Apron	April 2020	1,700

2021

Airport	Consultant	Project	Estimated Bid Schedule	Estimated Quantity
Larger Projects				
Northern CO Regional	Dibble	Construct Taxiway/Apron	April 2021	

Granby, CO	Armstrong	Construct Taxilanes	April 2021	
Grand Junction, CO	Garver	Rehabilitate Taxiway		
Lamar, CO		Rehabilitate Taxiway		3,500
Rocky Mountain Metro	Jviation	Rehabilitate Taxiway		10,000
Jackson, WY	Jviation	Reconstruct Runway	Late 2020/Early 2021 for Mobilization in 2021, Construction in 2022	65,000
Riverton, WY	Jviation	Rehabilitate Taxiway	Mid-2021 for 2022 Construction	17,500

FAA Airport Improvement Program Grant Detail Report

As of 6/08/2018

State	City	Worksite	LocID	Grant Number	Sponsor	Current Grant Totals Note: If there is no award date, the grant has only been announced, and the totals are preliminary estimates, subject to change prior to award Entitlement Amount	Discretionary Amount	Total AIP Amount	Project Summary
CO	Colorado Springs	City of Colorado Springs Municipal	COS	3-08-0010-062-2018	City of Colorado Springs	$ 3,181,131	$ 7,296,790	$ 10,477,921	Reconstruct Taxiway
CO	Denver	Denver International	DEN	3-08-0086-092-2018	County and City of Denver	$ 500,000	$ 7,000,000	$ 7,500,000	Rehabilitate Taxiway, Rehabilitate Taxiway Lighting
CO	Denver	Denver International	DEN	3-08-0086-093-2018	County and City of Denver	$ 4,704,073	$ 2,000,000	$ 6,704,073	Rehabilitate Runway - 07/25, Rehabilitate Runway Lighting - 07/25, Rehabilitate Taxiway, Rehabilitate Taxiway Lighting
CO	Grand Junction	Grand Junction Regional	GJT	3-08-0027-057-2018	City Gr.Junc./Co.Mesa/Walker Fld.Pub.AirportAuth.	$ -	$ 3,225,000	$ 3,225,000	Construct Runway - 11/29
CO	Grand Junction	Grand Junction Regional	GJT	3-08-0027-058-2018	City Gr.Junc./Co.Mesa/Walker Fld.Pub.AirportAuth.	$ 191,494	$ 1,775,000	$ 1,966,494	Construct Runway - 11/29
CO	Hayden	Yampa Valley	HDN	3-08-0031-044-2018	County of Routt	$ 1,439,029	$ 2,990,971	$ 4,430,000	Construct Apron, Rehabilitate Apron
WY	Casper	Casper/Natrona County International	CPR	3-56-0004-058-2018	County of Natrona Board of Trustees	$ 1,225,172	$ 1,435,000	$ 2,660,172	Rehabilitate Taxiway
WY	Cody	Yellowstone Regional	COD	3-56-0006-039-2018	City of Cody	$ 398,745	$ -	$ 398,745	Update Airport Master Plan Study
WY	Cody	Yellowstone Regional	COD	3-56-0006-038-2018	City of Cody	$ 1,297,681	$ -	$ 1,297,681	Expand Apron
WY	Dubois	Dubois Municipal	DUB	3-56-0010-019-2018	Town of Dubois	$ 80,000	$ -	$ 80,000	Install Miscellaneous NAVAIDS, Rehabilitate Apron
WY	Fort Bridger	Fort Bridger	FBR	3-56-0042-013-2018	County of Uinta	$ 565,048	$ -	$ 565,048	Rehabilitate Apron
WY	Laramie	Laramie Regional	LAR	3-56-0017-036-2018	Laramie Regional Airport	$ 1,321,878	$ 3,128,122	$ 4,450,000	Rehabilitate Runway - 03/21, Rehabilitate Runway Lighting - 03/21
WY	Pinedale	Ralph Wenz Field	PNA	3-56-0021-021-2018	Town of Pinedale	$ 181,773	$ -	$ 181,773	Rehabilitate Apron
WY	Rawlins	Rawlins Municipal/Harvey Field	RWL	3-56-0023-017-2018	City of Rawlins	$ 302,653	$ -	$ 302,653	Update Airport Master Plan Study
WY	Riverton	Riverton Regional	RIW	3-56-0024-045-2018	City of Riverton	$ 1,816,117	$ -	$ 1,816,117	Rehabilitate Apron
WY	Thermopolis	Hot Springs County	HSG	3-56-0043-010-2018	County of Hot Springs	$ 150,000	$ -	$ 150,000	Improve Airport Drainage

FAA Airport Improvement Program Grant Detail Report

As of 6/08/2018

State	City	Worksite	LocID	Grant Number	Sponsor	Announcement Date	Award Date	Current Grant Totals Note: If there is no award date, the grant has only been announced, and the totals are preliminary estimates, subject to change prior to award Entitlement Amount	Discretionary Amount	Total AIP Amount	Project Summary
AK	Anchorage	Lake Hood	LHD	3-02-0013-023-2018	State of Alaska/Department of Transportation & Public Facilities	6/8/2018		$ 1,000,000	$ 6,406,144	$ 7,406,144	Reconstruct Taxiway
AK	Anchorage	Ted Stevens Anchorage International	ANC	3-02-0016-186-2018	State of Alaska/Department of Transportation & Public Facilities	6/8/2018		$ -	$ 4,000,000	$ 4,000,000	Acquire Snow Removal Equipment
AK	Anchorage	Ted Stevens Anchorage International	ANC	3-02-0016-189-2018	State of Alaska/Department of Transportation & Public Facilities	6/8/2018		$ -	$ 400,000	$ 400,000	Improve Airport Miscellaneous Improvements
AK	Anchorage	Ted Stevens Anchorage International	ANC	3-02-0016-185-2018	State of Alaska/Department of Transportation & Public Facilities	6/8/2018		$ -	$ 8,000,000	$ 8,000,000	Widen Taxiway
AK	Juneau	Juneau International	JNU	3-02-0133-076-2018	City and Borough of Juneau	6/8/2018		$ 2,000,000	$ -	$ 2,000,000	Improve Terminal Building
AK	Juneau	State of Alaska	*AKS	3-02-0000-024-2018	State of Alaska/Department of Transportation & Public Facilities	6/8/2018		$ 2,000,000	$ -	$ 2,000,000	Update Miscellaneous Study, Update State System Plan Study
AK	Kiana	Bob Baker Memorial	IAN	3-02-0146-004-2018	State of Alaska/Department of Transportation & Public Facilities	6/8/2018		$ 1,850,000	$ 4,669,685	$ 6,519,685	Construct Taxiway, Extend Runway - 06/24, Reconstruct Runway - 06/24, Reconstruct Runway Lighting - 06/24, Rehabilitate Apron
AK	King Salmon	King Salmon	AKN	3-02-0148-017-2018	State of Alaska/Department of Transportation & Public Facilities	6/8/2018		$ 1,500,000	$ 11,309,336	$ 12,809,336	Rehabilitate Runway - 12/30, Rehabilitate Taxiway
AK	King Salmon	King Salmon	AKN	3-02-0148-018-2018	State of Alaska/Department of Transportation & Public Facilities	6/8/2018		$ 1,625,000	$ -	$ 1,625,000	Install Perimeter Fencing required by 49 CFR 1542
AK	Sitka	Sitka Rocky Gutierrez	SIT	3-02-0268-032-2018	State of Alaska/Department of Transportation & Public Facilities	6/8/2018		$ 400,000	$ -	$ 400,000	Acquire Land for Development
AL	Birmingham	Birmingham-Shuttlesworth International	BHM	3-01-0014-100-2018	Birmingham Airport Authority	6/8/2018		$ 1,417,500	$ -	$ 1,417,500	Acquire Aircraft Rescue & Fire Fighting Safety Equipment, Improve Airport Erosion Control, Install Miscellaneous NAVAIDS, Install Runway Distance-To-Go Signs - 06/24, Install Runway Distance-To-Go Signs - 18/36, Rehabilitate Runway Lighting - 06/24, Rehabilitate Taxiway
AL	Decatur	Pryor Field Regional	DCU	3-01-0024-027-2018	Counties of Morgan and Limestone	6/8/2018		$ 495,900	$ -	$ 495,900	Reconstruct Taxiway Lighting
AL	Fairhope	H. L. (Sonny) Callahan	CQF	3-01-0029-019-2018	City of Fairhope	6/8/2018		$ 233,757	$ 2,800,000	$ 3,033,757	Construct Taxiway
AR	Fayetteville/Springdale/Rogers	Northwest Arkansas Regional	XNA	3-05-0021-054-2018	Northwest Arkansas Regional Airport Authority	6/8/2018		$ 7,920,688	$ 5,688,834	$ 13,609,522	Rehabilitate Taxiway
AR	Mena	Mena Intermountain Municipal	MEZ	3-05-0041-020-2018	City of Mena	6/8/2018		$ 1,042,845	$ 2,430,000	$ 3,472,845	Rehabilitate Taxiway
AR	Springdale	Springdale Municipal	ASG	3-05-0059-019-2018	City of Springdale	6/8/2018		$ 879,499	$ 2,000,000	$ 2,879,499	Reconstruct Runway Lighting - 18/36, Rehabilitate Runway - 18/36
AR	Stuttgart	Stuttgart Municipal Carl Humphrey Field	SGT	3-05-0061-025-2018	City of Stuttgart	6/8/2018		$ 246,921	$ 750,000	$ 996,921	Rehabilitate Runway - 18/36
AZ	Phoenix	Phoenix Sky Harbor International	PHX	3-04-0029-087-2018	City of Phoenix	6/8/2018		$ 7,189,395	$ -	$ 7,189,395	Reconstruct Apron
AZ	Show Low	Show Low Regional	SOW	3-04-0035-027-2018	City of Show Low	6/8/2018		$ 235,370	$ 1,819,057	$ 2,054,427	Rehabilitate Runway - 06/24
AZ	Wickenburg	Wickenburg Municipal	E25	3-04-0048-024-2018	Town of Wickenburg	6/8/2018		$ 1,061,750	$ -	$ 1,061,750	Construct Apron
CA	Fresno	Fresno Yosemite International	FAT	3-06-0087-081-2018	City of Fresno	6/8/2018		$ 3,795,449	$ 5,324,521	$ 9,119,970	Rehabilitate Taxiway
CA	Napa	Napa County	APC	3-06-0162-038-2018	County of Napa	6/8/2018		$ 217,419	$ 15,500,000	$ 15,717,419	Rehabilitate Runway - 18L/36R, Rehabilitate Runway - 18R/36L
CA	San Diego	San Diego International	SAN	3-06-0214-079-2018	San Diego County Regional Airport Authority	6/8/2018		$ 3,169,008	$ 9,000,000	$ 12,169,008	Rehabilitate Taxiway
CA	San Jose	Norman Y Mineta San Jose International	SJC	3-06-0226-096-2018	City of San Jose	6/8/2018		$ -	$ 10,262,904	$ 10,262,904	Reconstruct Apron
CA	Santa Maria	Santa Maria Public/Capt G Allan Hancock Field	SMX	3-06-0237-036-2018	Santa Maria Public Airport District	6/8/2018		$ 2,000,000	$ 1,000,000	$ 3,000,000	Rehabilitate Apron
CO	Colorado Springs	City of Colorado Springs Municipal	COS	3-08-0010-062-2018	City of Colorado Springs	6/8/2018		$ 3,181,131	$ 7,296,790	$ 10,477,921	Reconstruct Taxiway
CO	Denver	Denver International	DEN	3-08-0086-092-2018	County and City of Denver	6/8/2018		$ 500,000	$ 7,000,000	$ 7,500,000	Rehabilitate Taxiway, Rehabilitate Taxiway Lighting
CO	Denver	Denver International	DEN	3-08-0086-093-2018	County and City of Denver	6/8/2018		$ 4,704,073	$ 2,000,000	$ 6,704,073	Rehabilitate Runway - 07/25, Rehabilitate Runway Lighting - 07/25, Rehabilitate Taxiway, Rehabilitate Taxiway Lighting
CO	Grand Junction	Grand Junction Regional	GJT	3-08-0027-057-2018	City Gr.Junc./Co.Mesa/Walker Fld.Pub.AirportAuth.	6/8/2018		$ -	$ 3,225,000	$ 3,225,000	Construct Runway - 11/29
CO	Grand Junction	Grand Junction Regional	GJT	3-08-0027-058-2018	City Gr.Junc./Co.Mesa/Walker Fld.Pub.AirportAuth.	6/8/2018		$ 191,494	$ 1,775,000	$ 1,966,494	Construct Runway - 11/29
CO	Hayden	Yampa Valley	HDN	3-08-0031-044-2018	County of Routt	6/8/2018		$ 1,439,029	$ 2,990,971	$ 4,430,000	Construct Apron, Rehabilitate Apron
DE	Dover/Cheswold	Delaware Airpark	33N	3-10-0001-022-2018	Delaware River and Bay Authority	6/8/2018		$ -	$ 300,000	$ 300,000	Acquire Land For Approaches
FL	Fort Lauderdale	Fort Lauderdale/Hollywood International	FLL	3-12-0025-083-2018	Broward County	6/8/2018		$ 402,511	$ 20,000,000	$ 20,402,511	Extend Runway [Letter of Intent] - 10R/28L
FL	Key West	Key West International	EYW	3-12-0037-056-2018	Monroe County Board of County Commissioners	6/8/2018		$ 1,692,000	$ -	$ 1,692,000	Modify Access Road, Rehabilitate Taxiway, Rehabilitate Taxiway Lighting
FL	Ormond Beach	Ormond Beach Municipal	OMN	3-12-0059-021-2018	City of Ormond Beach	6/8/2018		$ 300,000	$ 1,250,000	$ 1,550,000	Rehabilitate Runway - 08/26, Rehabilitate Runway Lighting - 08/26
FL	Titusville	Space Coast Regional	TIX	3-12-0080-028-2018	Titusville-Cocoa Airport Authority	6/8/2018		$ 332,419	$ 1,427,981	$ 1,760,400	Rehabilitate Runway Lighting - 09/27, Rehabilitate Runway Lighting - 18/36

State	City	Worksite	LocID	Grant Number	Sponsor	Announcement Date	Award Date	Current Grant Totals Note: If there is no award date, the grant has only been announced, and the totals are preliminary estimates, subject to change prior to award Entitlement Amount	Discretionary Amount	Total AIP Amount	Project Summary
GA	Atlanta	Georgia State Block Grant Program	*GAB	3-13-SBGP-022-2018	State of Georgia	6/8/2018		$ 18,207,688	$ -	$ 18,207,688	Non primary development projects in state block grant program
GA	Atlanta	Georgia State Block Grant Program	*GAB	3-13-SBGP-024-2018	State of Georgia	6/8/2018		$ -	$ 9,500,000	$ 9,500,000	Non primary development projects in state block grant program
IA	Ankeny	Ankeny Regional	IKV	3-19-0132-024-2018	Polk County Aviation Authority	6/8/2018		$ 150,000	$ 1,135,578	$ 1,285,578	Reconstruct Taxiway, Rehabilitate Taxiway
IA	Atlantic	Atlantic Municipal	AIO	3-19-0005-013-2018	City of Atlantic	6/8/2018		$ 577,000	$ -	$ 577,000	Expand Apron, Rehabilitate Apron
IA	Belle Plaine	Belle Plaine Municipal	TZT	3-19-0131-009-2018	City of Belle Plaine	6/8/2018		$ 150,000	$ -	$ 150,000	Rehabilitate Runway - 18/36
IA	Boone	Boone Municipal	BNW	3-19-0009-016-2018	Boone Airport Commission	6/8/2018		$ 262,359	$ -	$ 262,359	Reconstruct Taxiway
IA	Burlington	Southeast Iowa Regional	BRL	3-19-0010-038-2018	Southeast Iowa Regional Airport Authority	6/8/2018		$ 351,948	$ 214,888	$ 566,836	Reconstruct Runway - 18/36
IA	Cedar Rapids	The Eastern Iowa	CID	3-19-0012-052-2018	The Cedar Rapids Airport Commission	6/8/2018		$ 3,442,122	$ -	$ 3,442,122	Improve Terminal Building
IA	Cedar Rapids	The Eastern Iowa	CID	3-19-0012-053-2018	The Cedar Rapids Airport Commission	6/8/2018		$ 407,711	$ -	$ 407,711	Reconstruct Deicing Pad with Associated Facilities
IA	Centerville	Centerville Municipal	TVK	3-19-0013-010-2018	City of Centerville	6/8/2018		$ 148,500	$ -	$ 148,500	Update Airport Master Plan Study
IA	Chariton	Chariton Municipal	CNC	3-19-0014-010-2018	City of Chariton	6/8/2018		$ 219,000	$ -	$ 219,000	Rehabilitate Apron, Rehabilitate Runway - 10/28, Rehabilitate Runway - 17/35, Rehabilitate Taxiway
IA	Cherokee	Cherokee County Regional	CKP	3-19-0099-014-2018	Cherokee, Iowa, Aviation Authority	6/8/2018		$ 130,500	$ -	$ 130,500	Construct Taxiway
IA	Clinton	Clinton Municipal	CWI	3-19-0019-020-2018	Clinton Airport Commission	6/8/2018		$ 382,500	$ -	$ 382,500	Reconstruct Taxiway
IA	Council Bluffs	Council Bluffs Municipal	CBF	3-19-0022-021-2018	Council Bluffs Airport Authority	6/8/2018		$ 150,000	$ -	$ 150,000	Construct Fuel Farm
IA	Davenport	Davenport Municipal	DVN	3-19-0024-020-2018	City of Davenport	6/8/2018		$ 271,551	$ 6,338,449	$ 6,610,000	Rehabilitate Runway - 15/33
IA	Des Moines	Des Moines International	DSM	3-19-0027-070-2018	Des Moines Airport Authority	6/8/2018		$ 4,597,754	$ 1,982,899	$ 6,580,653	Rehabilitate Runway - 13/31, Rehabilitate Taxiway
IA	Dubuque	Dubuque Regional	DBQ	3-19-0028-064-2018	Dubuque Regional Airport Commission	6/8/2018		$ 1,132,090	$ -	$ 1,132,090	Acquire Snow Removal Equipment
IA	Fairfield	Fairfield Municipal	FFL	3-19-0033-016-2018	City of Fairfield	6/8/2018		$ 342,000	$ -	$ 342,000	Reconstruct Taxiway
IA	Forest City	Forest City Municipal	FXY	3-19-0034-017-2018	City of Forest City	6/8/2018		$ 225,000	$ -	$ 225,000	Reconstruct Runway Lighting - 15/33
IA	Greenfield	Greenfield Municipal	GFZ	3-19-0038-008-2018	City of Greenfield	6/8/2018		$ 225,000	$ -	$ 225,000	Reconstruct Runway Lighting - 07/25
IA	Guthrie Center	Guthrie County Regional	GCT	3-19-0103-010-2018	Guthrie County Airport Authority	6/8/2018		$ 145,000	$ -	$ 145,000	Reconstruct Runway - 18/36
IA	Independence	Independence Municipal	IIB	3-19-0045-015-2018	City of Independence	6/8/2018		$ 58,500	$ -	$ 58,500	Construct Taxiway
IA	Jefferson	Jefferson Municipal	EFW	3-19-0049-011-2018	City of Jefferson	6/8/2018		$ 50,000	$ -	$ 50,000	Extend Runway - 14/32
IA	Knoxville	Knoxville Municipal	OXV	3-19-0051-015-2018	Knoxville Airport Commission	6/8/2018		$ 300,000	$ -	$ 300,000	Reconstruct Runway - 15/33
IA	Le Mars	Le Mars Municipal	LRJ	3-19-0127-014-2018	City of Le Mars	6/8/2018		$ 50,000	$ -	$ 50,000	Extend Runway - 18/36
IA	Le Mars	Le Mars Municipal	LRJ	3-19-0127-013-2018	City of Le Mars	6/8/2018		$ 359,428	$ -	$ 359,428	Extend Runway - 18/36
IA	Manchester	Manchester Municipal	C27	3-19-0137-001-2018	City of Manchester	6/8/2018		$ 80,100	$ -	$ 80,100	Conduct Environmental Study
IA	Monticello	Monticello Regional	MXO	3-19-0061-009-2018	City of Monticello	6/8/2018		$ 150,000	$ -	$ 150,000	Update Airport Master Plan Study
IA	Oelwein	Oelwein Municipal	OLZ	3-19-0067-009-2018	City of Oelwein	6/8/2018		$ 329,400	$ -	$ 329,400	Construct Taxiway
IA	Sheldon	Sheldon Regional	SHL	3-19-0081-015-2018	City of Sheldon	6/8/2018		$ 260,640	$ -	$ 260,640	Construct Snow Removal Equipment Building
IA	Storm Lake	Storm Lake Municipal	SLB	3-19-0088-013-2018	City of Storm Lake	6/8/2018		$ 80,000	$ -	$ 80,000	Rehabilitate Apron, Rehabilitate Taxiway
IA	Washington	Washington Municipal	AWG	3-19-0093-010-2018	City of Washington	6/8/2018		$ 269,158	$ -	$ 269,158	Expand Apron
IA	Waterloo	Waterloo Regional	ALO	3-19-0094-046-2018	City of Waterloo, Iowa	6/8/2018		$ 510,480	$ -	$ 510,480	Reconstruct Apron
IA	Waverly	Waverly Municipal	C25	3-19-0096-009-2018	City of Waverly	6/8/2018		$ 122,400	$ -	$ 122,400	Extend Runway - 11/29
IA	West Union	George L Scott Municipal	3Y2	3-19-0128-008-2018	City of West Union Airport Commission	6/8/2018		$ 300,000	$ -	$ 300,000	Construct Fuel Farm
ID	Caldwell	Caldwell Industrial	EUL	3-16-0045-030-2018	City of Caldwell	6/8/2018		$ 454,741	$ 1,693,265	$ 2,148,006	Rehabilitate Runway - 12/30, Rehabilitate Taxiway
IL	Chicago/Rockford	Chicago/Rockford International	RFD	3-17-0088-081-2018	Greater Rockford Airport Authority	6/8/2018		$ 1,963,582	$ 1,200,000	$ 3,163,582	Expand Apron
IL	Chicago/Rockford	Chicago/Rockford International	RFD	3-17-0088-082-2018	Greater Rockford Airport Authority	6/8/2018		$ -	$ 2,000,000	$ 2,000,000	Expand Terminal Building
IL	Quincy	Quincy Regional-Baldwin Field	UIN	3-17-0085-039-2018	City of Quincy	6/8/2018		$ 1,000,000	$ 1,100,000	$ 2,100,000	Reconstruct Runway - 13/31
IL	Springfield	Abraham Lincoln Capital	SPI	3-17-0096-072-2018	Springfield Airport Authority	6/8/2018		$ 1,229,998	$ 3,400,000	$ 4,629,998	Improve Terminal Building
IN	Anderson	Anderson Municipal-Darlington Field	AID	3-18-0001-032-2018	City of Anderson	6/8/2018		$ 150,000	$ 2,557,500	$ 2,707,500	Rehabilitate Runway - 12/30, Rehabilitate Runway Lighting - 12/30
IN	Fort Wayne	Fort Wayne International	FWA	3-18-0022-070-2018	Fort Wayne-Allen County Airport Authority	6/8/2018		$ 2,794,716	$ 2,646,004	$ 5,440,720	Rehabilitate Runway - 05/23
IN	Gary	Gary/Chicago International	GYY	3-18-0028-038-2018	Gary/Chicago Airport Authority	6/8/2018		$ 150,000	$ 4,600,000	$ 4,750,000	Rehabilitate Runway - 12/30
IN	Indianapolis	Eagle Creek Airpark	EYE	3-18-0039-024-2018	Indianapolis Airport Authority	6/8/2018		$ 150,000	$ 2,675,000	$ 2,825,000	Construct Taxiway
IN	Kokomo	Kokomo Municipal	OKK	3-18-0044-027-2018	Kokomo Board of Aviation Commissioners	6/8/2018		$ 150,000	$ 210,000	$ 360,000	Rehabilitate Taxiway
IN	Paoli	Paoli Municipal	I42	3-18-0064-015-2018	City of Paoli	6/8/2018		$ 332,500	$ 500,000	$ 832,500	Extend Runway - 02/20
KS	Beloit	Moritz Memorial	K61	3-20-0008-012-2018	City of Beloit	6/8/2018		$ 150,000	$ -	$ 150,000	Update Airport Master Plan Study
KS	Burlington	Coffey County	UKL	3-20-0510-012-2018	Coffey County Airport Authority	6/8/2018		$ 225,000	$ -	$ 225,000	Reconstruct Runway - 18/36
KS	Chanute	Chanute Martin Johnson	CNU	3-20-0009-013-2018	City of Chanute	6/8/2018		$ 200,520	$ -	$ 200,520	Rehabilitate Taxiway [Parallel], Rehabilitate Taxiway [Taxilane]
KS	Colby	Shalz Field	CBK	3-20-0012-018-2018	City of Colby	6/8/2018		$ 243,757	$ -	$ 243,757	Rehabilitate Runway - 17/35

State	City	Worksite	LocID	Grant Number	Sponsor	Announcement Date	Award Date	Current Grant Totals Note: If there is no award date, the grant has only been announced, and the totals are preliminary estimates, subject to change prior to award Entitlement Amount	Discretionary Amount	Total AIP Amount	Project Summary
KS	Concordia	Blosser Municipal	CNK	3-20-0013-012-2018	City of Concordia	6/8/2018		$ 247,447	$ -	$ 247,447	Reconstruct Access Road, Reconstruct Parking Lot
KS	Emporia	Emporia Municipal	EMP	3-20-0020-012-2018	City of Emporia	6/8/2018		$ 360,000	$ -	$ 360,000	Acquire Land For Approaches
KS	Gardner	Gardner Municipal	K34	3-20-0119-014-2018	City of Gardner	6/8/2018		$ 518,528	$ -	$ 518,528	Acquire Land For Approaches
KS	Garnett	Garnett Municipal	K68	3-20-0025-009-2018	City of Garnett	6/8/2018		$ 180,000	$ -	$ 180,000	Update Airport Master Plan Study
KS	Herington	Herington Regional	HRU	3-20-0029-009-2018	City of Herington	6/8/2018		$ 219,141	$ -	$ 219,141	Install Miscellaneous NAVAIDS, Install Taxiway Lighting
KS	Hill City	Hill City Municipal	HLC	3-20-0031-016-2018	City of Hill City	6/8/2018		$ 559,346	$ -	$ 559,346	Reconstruct Taxiway
KS	Independence	Independence Municipal	IDP	3-20-0036-023-2018	City of Independence	6/8/2018		$ 252,810	$ -	$ 252,810	Rehabilitate Runway - 04/22, Rehabilitate Taxiway
KS	Kingman	Kingman Airport - Clyde Cessna Field	9K8	3-20-0042-017-2018	City of Kingman	6/8/2018		$ 225,000	$ -	$ 225,000	Update Airport Master Plan Study
KS	Leoti	Mark Hoard Memorial	3K7	3-20-0049-007-2018	Leoti Airport, Inc	6/8/2018		$ 600,000	$ -	$ 600,000	Install Airport Beacons, Install Miscellaneous NAVAIDS, Install Runway Vertical/Visual Guidance System - 17/35, Install Taxiway Lighting, Reconstruct Runway - 17/35
KS	Liberal	Liberal Mid-America Regional	LBL	3-20-0050-023-2018	City of Liberal	6/8/2018		$ 802,222	$ -	$ 802,222	Acquire Snow Removal Equipment
KS	Liberal	Liberal Mid-America Regional	LBL	3-20-0050-024-2018	City of Liberal	6/8/2018		$ 756,000	$ -	$ 756,000	Reconstruct Taxiway, Rehabilitate Apron, Rehabilitate Building
KS	Manhattan	Manhattan Regional	MHK	3-20-0052-049-2018	City of Manhattan	6/8/2018		$ 450,000	$ -	$ 450,000	Update Airport Master Plan Study
KS	Newton	Newton-City-County	EWK	3-20-0058-033-2018	City of Newton/County of Harvey	6/8/2018		$ 191,160	$ -	$ 191,160	Rehabilitate Taxiway
KS	Ottawa	Ottawa Municipal	OWI	3-20-0066-014-2018	City of Ottawa	6/8/2018		$ 400,000	$ -	$ 400,000	Install Taxiway Lighting
KS	Parsons	Tri-City	PPF	3-20-0067-011-2018	City of Parsons	6/8/2018		$ 642,263	$ -	$ 642,263	Reconstruct Airport Beacon, Rehabilitate Runway - 17/35
KS	Phillipsburg	Phillipsburg Municipal	PHG	3-20-0068-013-2018	City of Phillipsburg	6/8/2018		$ 463,973	$ -	$ 463,973	Construct Taxiway
KS	Pittsburg	Atkinson Municipal	PTS	3-20-0069-018-2018	City of Pittsburg	6/8/2018		$ 300,600	$ -	$ 300,600	Rehabilitate Runway - 04/22
KS	Russell	Russell Municipal	RSL	3-20-0071-012-2018	City of Russell	6/8/2018		$ 405,000	$ -	$ 405,000	Install Runway Vertical/Visual Guidance System - 17/35, Reconstruct Runway Lighting - 17/35, Reconstruct Taxiway Lighting
KS	Salina	Salina Regional	SLN	3-20-0072-039-2018	Salina Airport Authority	6/8/2018		$ 886,500	$ -	$ 886,500	Acquire Aircraft Rescue & Fire Fighting Vehicle
KS	Smith Center	Smith Center Municipal	K82	3-20-0076-014-2018	City of Smith Center	6/8/2018		$ 423,000	$ -	$ 423,000	Construct Taxiway, Install Airfield Guidance Signs
KS	Syracuse	Syracuse-Hamilton County Municipal	3K3	3-20-0081-012-2018	County of Hamilton	6/8/2018		$ 301,500	$ -	$ 301,500	Rehabilitate Runway - 18/36, Rehabilitate Taxiway
KS	Topeka	State of Kansas	*KSS	3-20-0000-019-2018	State of Kansas - Department of Transportation	6/8/2018		$ -	$ 453,600	$ 453,600	Update State System Plan Study
KS	Ulysses	Ulysses	ULS	3-20-0084-016-2018	County of Grant	6/8/2018		$ 486,000	$ -	$ 486,000	Construct Building
KS	Wichita	Colonel James Jabara	AAO	3-20-0089-023-2018	Wichita Airport Authority	6/8/2018		$ 471,214	$ -	$ 471,214	Acquire Land For Approaches
KS	Wichita	Wichita Dwight D Eisenhower National	ICT	3-20-0088-074-2018	Wichita Airport Authority	6/8/2018		$ 560,509	$ -	$ 560,509	Construct Apron
KS	Wichita	Wichita Dwight D Eisenhower National	ICT	3-20-0088-076-2018	Wichita Airport Authority	6/8/2018		$ 1,525,500	$ -	$ 1,525,500	Acquire Aircraft Rescue & Fire Fighting Vehicle [Vehicle 4], Acquire Aircraft Rescue & Fire Fighting Vehicle [Vehicle 5], Acquire Friction Measuring Equipment
KS	Wichita	Wichita Dwight D Eisenhower National	ICT	3-20-0088-075-2018	Wichita Airport Authority	6/8/2018		$ 744,368	$ -	$ 744,368	Rehabilitate Taxiway Lighting
KS	Wichita	Wichita Dwight D Eisenhower National	ICT	3-20-0088-077-2018	Wichita Airport Authority	6/8/2018		$ 1,122,787	$ -	$ 1,122,787	Construct Taxiway, Expand Apron
LA	Baton Rouge	Baton Rouge Metropolitan, Ryan Field	BTR	3-22-0006-110-2018	Parish of East Baton Rouge/City of Baton Rouge	6/8/2018		$ 218,395	$ 3,800,000	$ 4,018,395	Improve Runway Safety Area - 13/31
MA	Beverly	Beverly Regional	BVY	3-25-0006-035-2018	City of Beverly	6/8/2018		$ 89,370	$ -	$ 89,370	Wildlife Hazard Assessments
MA	Beverly	Beverly Regional	BVY	3-25-0006-036-2018	City of Beverly	6/8/2018		$ 66,690	$ -	$ 66,690	Update Airport Master Plan Study
MA	Beverly	Beverly Regional	BVY	3-25-0006-037-2018	City of Beverly	6/8/2018		$ 52,470	$ -	$ 52,470	Remove Obstructions [Non-Hazard]
MA	Boston	General Edward Lawrence Logan International	BOS	3-25-0010-128-2018	Massachusetts Port Authority	6/8/2018		$ 5,892,650	$ -	$ 5,892,650	Rehabilitate Taxiway
MA	Chatham	Chatham Municipal	CQX	3-25-0015-023-2018	Town of Chatham	6/8/2018		$ 328,500	$ -	$ 328,500	Update Airport Master Plan Study
MA	Mansfield	Mansfield Municipal	1B9	3-25-0028-033-2018	Town of Mansfield	6/8/2018		$ 150,000	$ -	$ 150,000	Conduct Miscellaneous Study
MA	Marshfield	Marshfield Municipal - George Harlow Field	GHG	3-25-0030-029-2018	Town of Marshfield	6/8/2018		$ 302,000	$ -	$ 302,000	Conduct Environmental Study
MA	Montague	Turners Falls	0B5	3-25-0032-020-2018	Town of Montague	6/8/2018		$ 247,500	$ -	$ 247,500	Acquire Snow Removal Equipment
MA	Provincetown	Provincetown Municipal	PVC	3-25-0043-044-2018	Town of Provincetown	6/8/2018		$ 2,970,000	$ -	$ 2,970,000	Environmental Mitigation [Service Roads Mitigation], Environmental Mitigation [Taxiway Mitigation], Rehabilitate Service Road, Rehabilitate Taxiway
MA	Worcester	Worcester Regional	ORH	3-25-0053-053-2018	Massachusetts Port Authority	6/8/2018		$ 1,000,000	$ -	$ 1,000,000	Rehabilitate Apron
MD	Leonardtown	St Mary's County Regional	2W6	3-24-0022-026-2018	County of St Mary's	6/8/2018		$ 150,000	$ 4,424,400	$ 4,574,400	Extend Runway [Grading/Drainage] - 11/29, Extend Runway [Remove Obstructions] - 11/29
ME	Auburn/Lewiston	Auburn/Lewiston Municipal	LEW	3-23-0002-025-2018	Cities of Auburn & Lewiston	6/8/2018		$ 300,000	$ -	$ 300,000	Reconstruct Runway - 17/35, Rehabilitate Runway - 04/22
ME	Machias	Machias Valley	MVM	3-23-0029-012-2018	Town of Machias	6/8/2018		$ 516,963	$ 2,536,737	$ 3,053,700	Reconstruct Runway - 18/36
MI	Grand Rapids	Gerald R Ford International	GRR	3-26-0039-056-2018	Gerald R Ford International Airport Authority	6/8/2018		$ 5,701,888	$ 13,000,000	$ 18,701,888	Rehabilitate Apron

								Current Grant Totals Note: If there is no award date, the grant has only been announced, and the totals are preliminary estimates, subject to change prior to award			
State	City	Worksite	LocID	Grant Number	Sponsor	Announcement Date	Award Date	Entitlement Amount	Discretionary Amount	Total AIP Amount	Project Summary
MI	Kalamazoo	Kalamazoo/Battle Creek International	AZO	3-26-0052-045-2018	County of Kalamazoo	6/8/2018		$ 2,125,161	$ 4,650,000	$ 6,775,161	Rehabilitate Runway - 17/35
MI	Saginaw	MBS International	MBS	3-26-0083-053-2018	Cities of Midland, Saginaw and County of Bay	6/8/2018		$ 4,657,264	$ 3,500,000	$ 8,157,264	Reconstruct Runway Lighting - 05/23, Rehabilitate Runway - 05/23
MN	Duluth	Sky Harbor	DYT	3-27-0025-013-2018	City of Duluth	6/8/2018		$ 150,000	$ 2,440,000	$ 2,590,000	Construct Runway - 14/32
MN	Minneapolis	Flying Cloud	FCM	3-27-0061-020-2018	Minneapolis-St. Paul Metropolitan Airports Commission	6/8/2018		$ 363,837	$ 1,136,163	$ 1,500,000	Install Airfield Guidance Signs, Install Runway Lighting - 10L/28R, Install Runway Vertical/Visual Guidance System - 10L/28R, Reconstruct Runway - 10L/28R
MO	Jefferson City	Missouri State Block Grant Program	*MOB	3-29-SBGP-092-2018	State of Missouri DOT	6/8/2018		$ 4,435,159	$ -	$ 4,435,159	Non primary development projects in state block grant program
MO	Jefferson City	Missouri State Block Grant Program	*MOB	3-29-SBGP-091-2018	State of Missouri DOT	6/8/2018		$ 8,550,000	$ -	$ 8,550,000	Non primary development projects in state block grant program
MO	Joplin	Joplin Regional	JLN	3-29-0037-038-2018	City of Joplin	6/8/2018		$ 95,000	$ -	$ 95,000	Update Miscellaneous Study
MO	Joplin	Joplin Regional	JLN	3-29-0037-039-2018	City of Joplin	6/8/2018		$ 522,500	$ -	$ 522,500	Acquire Aircraft Rescue & Fire Fighting Vehicle
MO	Kansas City	Charles B Wheeler Downtown	MKC	3-29-0041-027-2018	City of Kansas City	6/8/2018		$ 765,000	$ -	$ 765,000	Reconstruct Taxiway
MP	Rota Island	Benjamin Taisacan Manglona International	GRO	3-69-0003-029-2018	Commonwealth Ports Authority	6/8/2018		$ 1,160,724	$ 2,724,179	$ 3,884,903	Install Perimeter Fencing required by 14 CFR 139
MS	Okolona	Okolona Municipal-Richard Stovall Field	5A4	3-28-0093-020-2018	City of Okolona	6/8/2018		$ 100,977	$ -	$ 100,977	Expand Apron, Remove Obstructions [Non-Hazard]
MS	Oxford	University-Oxford	UOX	3-28-0057-032-2018	University of Mississippi	6/8/2018		$ 165,719	$ -	$ 165,719	Reconstruct Apron
MS	Philadelphia	Philadelphia Municipal	MPE	3-28-0059-018-2018	City of Philadelphia	6/8/2018		$ 230,400	$ -	$ 230,400	Install Perimeter Fencing not Required by 49 CFR 1542, Rehabilitate Apron
MS	Picayune	Picayune Municipal	MJD	3-28-0060-020-2018	City of Picayune	6/8/2018		$ 629,550	$ -	$ 629,550	Construct Taxiway, Install Taxiway Lighting
MS	Ripley	Ripley	25M	3-28-0066-011-2018	City of Ripley and County of Tippah	6/8/2018		$ 294,107	$ -	$ 294,107	Install Perimeter Fencing not Required by 49 CFR 1542
MS	Vicksburg	Vicksburg Municipal	VKS	3-28-0073-010-2018	City of Vicksburg	6/8/2018		$ 371,052	$ -	$ 371,052	Improve Airport Drainage
MS	West Point	McCharen Field	M83	3-28-0077-015-2018	City of West Point	6/8/2018		$ 358,380	$ -	$ 358,380	Expand Apron, Improve Airport Drainage
MS	Wiggins	Dean Griffin Memorial	M24	3-28-0078-018-2018	Wiggins-Stone County Airport Board	6/8/2018		$ 71,901	$ -	$ 71,901	Rehabilitate Apron, Rehabilitate Runway - 17/35, Rehabilitate Taxiway
MS	Yazoo City	Yazoo County	87I	3-28-0102-017-2018	County of Yazoo	6/8/2018		$ 150,000	$ -	$ 150,000	Construct Fuel Farm
NC	Asheville	Asheville Regional	AVL	3-37-0005-051-2018	Greater Asheville Regional Airport Authority	6/8/2018		$ 1,200,000	$ -	$ 1,200,000	Acquire Snow Removal Equipment, Security Enhancements
NC	Charlotte	Charlotte/Douglas International	CLT	3-37-0012-079-2018	City of Charlotte	6/8/2018		$ 12,602,171	$ -	$ 12,602,171	Expand Apron
NE	Alliance	Alliance Municipal	AIA	3-31-0003-020-2018	City of Alliance	6/8/2018		$ 2,700,000	$ -	$ 2,700,000	Rehabilitate Runway - 08/26
NE	Aurora	Aurora Municipal - Al Potter Field	AUH	3-31-0007-012-2018	Aurora Airport Authority	6/8/2018		$ 1,675,659	$ 897,341	$ 2,573,000	Reconstruct Runway - 16/34
NE	Beatrice	Beatrice Municipal	BIE	3-31-0009-017-2018	Beatrice Airport Authority	6/8/2018		$ 234,000	$ 2,434,000	$ 2,668,000	Install Runway Vertical/Visual Guidance System - 14/32, Reconstruct Runway - 14/32, Rehabilitate Runway Lighting - 14/32
NE	Broken Bow	Broken Bow Municipal/Keith Glaze Field	BBW	3-31-0013-009-2018	Joint Airport Authority for Broken Bow and Custer County, NE	6/8/2018		$ 180,000	$ -	$ 180,000	Rehabilitate Runway - 14/32
NE	Burwell	Cram Field	BUB	3-31-0014-007-2018	Burwell Airport Authority	6/8/2018		$ 270,000	$ -	$ 270,000	Construct Fuel Farm
NE	Chadron	Chadron Municipal	CDR	3-31-0017-016-2018	City of Chadron	6/8/2018		$ 591,790	$ -	$ 591,790	Construct Building
NE	Creighton	Creighton Municipal	6K3	3-31-0089-010-2018	Creighton Airport Authority	6/8/2018		$ 558,000	$ -	$ 558,000	Construct Building
NE	Grand Island	Central Nebraska Regional	GRI	3-31-0034-040-2018	Hall County Airport Authority	6/8/2018		$ 817,000	$ -	$ 817,000	Acquire Snow Removal Equipment
NE	Hastings	Hastings Municipal	HSI	3-31-0040-015-2018	City of Hastings	6/8/2018		$ 191,250	$ -	$ 191,250	Rehabilitate Building
NE	Imperial	Imperial Municipal	IML	3-31-0044-013-2018	Imperial Airport Authority	6/8/2018		$ 225,000	$ -	$ 225,000	Rehabilitate Building
NE	Lincoln	State of Nebraska	*NES	3-31-0000-025-2018	Nebraska Department of Transportation	6/8/2018		$ -	$ 67,500	$ 67,500	Update State System Plan Study
NE	North Platte	North Platte Regional Airport Lee Bird Field	LBF	3-31-0059-034-2018	North Platte Airport Authority	6/8/2018		$ 387,000	$ -	$ 387,000	Expand Aircraft Rescue & Fire Fighting Building
NE	North Platte	North Platte Regional Airport Lee Bird Field	LBF	3-31-0059-035-2018	North Platte Airport Authority	6/8/2018		$ 675,000	$ -	$ 675,000	Acquire Aircraft Rescue & Fire Fighting Vehicle
NE	Ord	Evelyn Sharp Field	ODX	3-31-0064-009-2018	Valley County Airport Authority	6/8/2018		$ 233,550	$ -	$ 233,550	Construct Parking Lot, Improve Access Road
NE	Oshkosh	Garden County	OKS	3-31-0065-011-2018	Garden County Airport	6/8/2018		$ 252,000	$ -	$ 252,000	Rehabilitate Runway - 12/30
NE	Pender	Pender Municipal	0C4	3-31-0066-010-2018	Pender Airport Authority	6/8/2018		$ 567,000	$ -	$ 567,000	Construct Building
NE	Scottsbluff	Western Nebraska Regional/William B Heilig Field	BFF	3-31-0072-041-2018	Airport Authority of the County of Scotts Bluff, Nebraska	6/8/2018		$ 900,000	$ -	$ 900,000	Acquire Aircraft Rescue & Fire Fighting Vehicle
NE	Superior	Superior Municipal	12K	3-31-0080-006-2018	Superior Airport Authority	6/8/2018		$ 265,500	$ -	$ 265,500	Construct Fuel Farm
NE	Tecumseh	Tecumseh Municipal	0G3	3-31-0081-011-2018	Tecumseh Airport Authority	6/8/2018		$ 579,600	$ -	$ 579,600	Construct Access Road, Install Miscellaneous NAVAIDS
NE	Thedford	Thomas County	TIF	3-31-0093-006-2018	Thomas County Airport Authority	6/8/2018		$ 600,000	$ -	$ 600,000	Construct Building
NE	Wahoo	Wahoo Municipal	AHQ	3-31-0085-012-2018	Wahoo Airport Authority	6/8/2018		$ 324,000	$ -	$ 324,000	Reconstruct Taxiway
NH	Concord	New Hampshire State Block Grant Program	*NHB	3-33-SBGP-027-2018	State of New Hampshire	6/8/2018		$ 2,166,377	$ -	$ 2,166,377	Non primary development projects in state block grant program
NH	Manchester	Manchester	MHT	3-33-0011-113-2018	City of Manchester	6/8/2018		$ 2,875,253	$ 6,802,001	$ 9,677,254	Reconstruct Taxiway
NJ	Atlantic City	Atlantic City International	ACY	3-34-0002-099-2018	South Jersey Transportation Authority	6/8/2018		$ 121,500	$ -	$ 121,500	Acquire Land For Approaches

								Current Grant Totals Note: If there is no award date, the grant has only been announced, and the totals are preliminary estimates, subject to change prior to award			
State	City	Worksite	LocID	Grant Number	Sponsor	Announcement Date	Award Date	Entitlement Amount	Discretionary Amount	Total AIP Amount	Project Summary
NJ	Morristown	Morristown Municipal	MMU	3-34-0023-054-2018	Town of Morristown	6/8/2018		$ 400,363	$ 2,099,637	$ 2,500,000	Improve Runway Safety Area - 05/23
NJ	Trenton	State of New Jersey	*NJS	3-34-0000-005-2018	State of New Jersey	6/8/2018		$ 900,000	$ -	$ 900,000	Update State System Plan Study
NM	Albuquerque	Albuquerque International Sunport	ABQ	3-35-0003-055-2018	City of Albuquerque	6/8/2018		$ 1,750,000	$ 2,500,000	$ 4,250,000	Reconstruct Taxiway
NM	Clayton	Clayton Municipal Airpark	CAO	3-35-0010-018-2018	Town of Clayton	6/8/2018		$ 482,875	$ 4,500,000	$ 4,982,875	Install Miscellaneous NAVAIDS, Rehabilitate Runway - 02/20
NV	Battle Mountain	Battle Mountain	BAM	3-32-0001-027-2018	County of Lander	6/8/2018		$ 150,000	$ 902,201	$ 1,052,201	Reconstruct Taxiway, Rehabilitate Runway - 03/21, Rehabilitate Runway - 12/30, Remove Obstructions [Non-Hazard]
NV	Elko	Elko Regional	EKO	3-32-0005-049-2018	City of Elko	6/8/2018		$ 1,000,000	$ 3,000,000	$ 4,000,000	Improve Airport Miscellaneous Improvements, Reconstruct Perimeter Fencing required by 49 CFR 1542
NV	Ely	Ely /Yelland Field/	ELY	3-32-0006-021-2018	County of White Pine	6/8/2018		$ 300,000	$ 10,950,000	$ 11,250,000	Rehabilitate Apron, Rehabilitate Runway - 18/36
NV	Lovelock	Derby Field	LOL	3-32-0011-016-2018	County of Pershing	6/8/2018		$ 450,000	$ -	$ 450,000	Acquire Snow Removal Equipment, Construct Snow Removal Equipment Building
NV	Silver Springs	Silver Springs	SPZ	3-32-0023-019-2018	County of Lyon	6/8/2018		$ 425,000	$ -	$ 425,000	Install Perimeter Fencing not Required by 49 CFR 1542, Install Weather Reporting Equipment
NV	Winnemucca	Winnemucca Municipal	WMC	3-32-0021-025-2018	City of Winnemucca	6/8/2018		$ 373,000	$ -	$ 373,000	Rehabilitate Apron, Rehabilitate Runway - 02/20, Rehabilitate Runway - 14/32, Rehabilitate Taxiway
NY	Albany	Albany International	ALB	3-36-0001-135-2018	Albany County Airport Authority	6/8/2018		$ 3,523,600	$ -	$ 3,523,600	Rehabilitate Terminal Building
NY	Bayport	Bayport Aerodrome	23N	3-36-0130-015-2018	Town of Islip	6/8/2018		$ 150,000	$ -	$ 150,000	Remove Obstructions [APP or DEP]
NY	Buffalo	Buffalo Niagara International	BUF	3-36-0009-096-2018	Niagara Frontier Transportation Authority	6/8/2018		$ 150,000	$ -	$ 150,000	Update Miscellaneous Study
NY	Jamestown	Chautauqua County/Jamestown	JHW	3-36-0048-048-2018	County of Chautauqua	6/8/2018		$ 150,000	$ -	$ 150,000	Conduct Airport Master Plan Study
NY	New York	Long Island MacArthur	ISP	3-36-0046-100-2018	Town of Islip	6/8/2018		$ 5,781,035	$ 8,499,998	$ 14,281,033	Rehabilitate Runway - 06/24
NY	Olean	Cattaraugus County-Olean	OLE	3-36-0091-024-2018	City of Olean	6/8/2018		$ 58,500	$ -	$ 58,500	Conduct Miscellaneous Study
NY	Poughkeepsie	Hudson Valley Regional	POU	3-36-0100-050-2018	County of Dutchess	6/8/2018		$ 169,500	$ 7,393,090	$ 7,562,590	Construct Aircraft Rescue & Fire Fighting Building, Construct Snow Removal Equipment Building
NY	Rome	Griffiss International	RME	3-36-0119-045-2018	County of Oneida	6/8/2018		$ 150,000	$ 7,575,000	$ 7,725,000	Improve Airport Miscellaneous Improvements, Reconstruct Runway - 15/33, Reconstruct Runway Lighting - 15/33
NY	Saranac Lake	Adirondack Regional	SLK	3-36-0105-069-2018	Town of Harrietstown	6/8/2018		$ 740,000	$ -	$ 740,000	Reconstruct Airfield Guidance Signs, Reconstruct Runway Lighting - 09/27, Reconstruct Taxiway Lighting
NY	Shirley	Brookhaven	HWV	3-36-0108-036-2018	Town of Brookhaven	6/8/2018		$ 90,000	$ -	$ 90,000	Reconstruct Airfield Guidance Signs, Reconstruct Runway Lighting - 06/24
NY	White Plains	Westchester County	HPN	3-36-0123-129-2018	County of Westchester	6/8/2018		$ 1,980,000	$ -	$ 1,980,000	Rehabilitate Terminal Building
NY	White Plains	Westchester County	HPN	3-36-0123-127-2018	County of Westchester	6/8/2018		$ 360,000	$ -	$ 360,000	Acquire Aircraft Deicing Equipment
NY	White Plains	Westchester County	HPN	3-36-0123-128-2018	County of Westchester	6/8/2018		$ 90,000	$ -	$ 90,000	Remove Obstructions [APP or DEP]
OH	Columbus	Rickenbacker International	LCK	3-39-0117-046-2018	Columbus Regional Airport Authority	6/8/2018		$ 2,011,319	$ 5,395,969	$ 7,407,288	Rehabilitate Taxiway
OK	Stillwater	Stillwater Regional	SWO	3-40-0090-026-2018	City of Stillwater	6/8/2018		$ 1,000,000	$ 1,500,000	$ 2,500,000	Reconstruct Runway Lighting - 04/22, Rehabilitate Runway - 04/22
OR	John Day	Grant County Regional/Ogilvie Field	GCD	3-41-0028-011-2018	Grant County	6/8/2018		$ 240,000	$ -	$ 240,000	Reconstruct Apron, Rehabilitate Apron
OR	McDermitt	McDermitt State	26U	3-41-0071-004-2018	Oregon Department of Aviation	6/8/2018		$ 150,000	$ -	$ 150,000	Install Airport Beacons, Reconstruct Runway - 16/34, Reconstruct Taxiway, Rehabilitate Runway Lighting - 16/34
OR	Scappoose	Scappoose Industrial Airpark	SPB	3-41-0056-024-2018	Port of St. Helens	6/8/2018		$ 747,413	$ 2,959,417	$ 3,706,830	Install Taxiway Lighting, Rehabilitate Taxiway
PA	Harrisburg	Harrisburg International	MDT	3-42-0059-083-2018	Susquehanna Area Regional Airport Authority	6/8/2018		$ 3,753,926	$ 2,746,074	$ 6,500,000	Rehabilitate Runway - 13/31
PA	Johnstown	John Murtha Johnstown-Cambria County	JST	3-42-0045-052-2018	Johnstown-Cambria County Airport Authority	6/8/2018		$ 180,000	$ -	$ 180,000	Acquire Land For Approaches
PA	Pittsburgh	Pittsburgh International	PIT	3-42-0081-123-2018	Allegheny County Airport Authority	6/8/2018		$ 2,074,612	$ 4,627,748	$ 6,702,360	Reconstruct Deicing Pad with Associated Facilities
SC	Clemson	Oconee County Regional	CEU	3-45-0016-024-2018	County of Oconee	6/8/2018		$ 421,203	$ -	$ 421,203	Acquire Land For Approaches, Expand Apron
SC	Greenville	Greenville Downtown	GMU	3-45-0026-027-2018	City of Greenville	6/8/2018		$ 519,000	$ 1,625,000	$ 2,144,000	Rehabilitate Runway Lighting - 01/19, Rehabilitate Taxiway Lighting, Update Airport Master Plan Study
SC	Lancaster	Lancaster County-Mc Whirter Field	LKR	3-45-0034-020-2018	County of Lancaster	6/8/2018		$ 131,846	$ -	$ 131,846	Install Runway Vertical/Visual Guidance System - 06/24, Rehabilitate Apron
SC	Pelion	Lexington County at Pelion	6J0	3-45-0067-017-2018	Lexington County	6/8/2018		$ 103,500	$ -	$ 103,500	Reconstruct Apron
TN	Knoxville	McGhee Tyson	TYS	3-47-0037-071-2018	Metropolitan Knoxville Airport Authority	6/8/2018		$ 4,091,871	$ 10,900,000	$ 14,991,871	Rehabilitate Runway - 05L/23R
TX	Austin	Texas State Block Grant Program	*TXB	3-48-SBGP-108-2018	Texas Department of Transportation - Aviation	6/8/2018		$ 19,556,720	$ -	$ 19,556,720	Non primary development projects in state block grant program
TX	Austin	Texas State Block Grant Program	*TXB	3-48-SBGP-109-2018	Texas Department of Transportation - Aviation	6/8/2018		$ 24,291,508	$ -	$ 24,291,508	Non primary development projects in state block grant program
UT	Beaver	Beaver Municipal	U52	3-49-0001-015-2018	City of Beaver	6/8/2018		$ 148,401	$ -	$ 148,401	Install Weather Reporting Equipment
UT	Logan	Logan-Cache	LGU	3-49-0016-030-2018	County of Cache	6/8/2018		$ 150,000	$ -	$ 150,000	Construct Taxiway
UT	Salt Lake City	Salt Lake City International	SLC	3-49-0033-114-2018	Salt Lake City Corporation	6/8/2018		$ 4,311,678	$ 12,000,000	$ 16,311,678	Rehabilitate Apron
UT	Wendover	Wendover	ENV	3-49-0046-030-2018	County of Tooele	6/8/2018		$ 500,000	$ -	$ 500,000	Update Airport Master Plan Study
VT	Burlington	Burlington International	BTV	3-50-0005-113-2018	City of Burlington	6/8/2018		$ 1,084,500	$ -	$ 1,084,500	Update Airport Master Plan Study
VT	Burlington	Burlington International	BTV	3-50-0005-114-2018	City of Burlington	6/8/2018		$ 2,292,155	$ -	$ 2,292,155	Rehabilitate Apron
WA	Pasco	Tri-Cities	PSC	3-53-0046-045-2018	Port of Pasco	6/8/2018		$ 1,876,365	$ 8,000,000	$ 9,876,365	Reconstruct Taxiway, Rehabilitate Taxiway
WA	Pasco	Tri-Cities	PSC	3-53-0046-046-2018	Port of Pasco	6/8/2018		$ 850,000	$ -	$ 850,000	Update Airport Master Plan Study

State	City	Worksite	LocID	Grant Number	Sponsor	Announcement Date	Award Date	Current Grant Totals Note: If there is no award date, the grant has only been announced, and the totals are preliminary estimates, subject to change prior to award Entitlement Amount	Discretionary Amount	Total AIP Amount	Project Summary
WA	Prosser	Prosser	S40	3-53-0050-018-2018	Port of Benton	6/8/2018		$ 281,109	$ -	$ 281,109	Construct Taxiway, Install Perimeter Fencing not Required by 49 CFR 1542
WA	Pullman/Moscow	Pullman/Moscow Regional	PUW	3-53-0051-048-2018	Cities of Pullman, WA and Moscow, ID	6/8/2018		$ 1,000,000	$ 6,800,000	$ 7,800,000	Construct Runway - 06/24
WA	Pullman/Moscow	Pullman/Moscow Regional	PUW	3-53-0051-047-2018	Cities of Pullman, WA and Moscow, ID	6/8/2018		$ -	$ 3,200,000	$ 3,200,000	Construct Runway - 06/24
WA	Richland	Richland	RLD	3-53-0056-030-2018	Port of Benton	6/8/2018		$ 260,000	$ -	$ 260,000	Construct Heliport/Helipad
WA	Spokane	Spokane International	GEG	3-53-0072-056-2018	County and City of Spokane	6/8/2018		$ 7,937,257	$ 8,027,986	$ 15,965,243	Install Airfield Guidance Signs, Install Runway Vertical/Visual Guidance System - 07/25, Rehabilitate Taxiway, Rehabilitate Taxiway Lighting
WI	Madison	Wisconsin State Block Grant Program	*WIB	3-55-SBGP-099-2018	State of Wisconsin	6/8/2018		$ -	$ 3,450,000	$ 3,450,000	Non primary development projects in state block grant program
WI	Madison	Wisconsin State Block Grant Program	*WIB	3-55-SBGP-098-2018	State of Wisconsin	6/8/2018		$ 15,749,071	$ -	$ 15,749,071	Non primary development projects in state block grant program
WV	Beckley	Raleigh County Memorial	BKW	3-54-0001-037-2018	Raleigh County Airport Authority	6/8/2018		$ 150,000	$ 3,850,000	$ 4,000,000	Rehabilitate Runway - 01/19
WV	Bluefield	Mercer County	BLF	3-54-0002-031-2018	Mercer County Airport Authority	6/8/2018		$ 270,860	$ 1,393,720	$ 1,664,580	Rehabilitate Runway - 05/23
WV	Charleston	Yeager	CRW	3-54-0003-062-2018	Central West Virginia Regional Airport Authority	6/8/2018		$ 1,974,098	$ 5,052,607	$ 7,026,705	Improve Runway Safety Area - 05/23
WV	Lewisburg	Greenbrier Valley	LWB	3-54-0012-038-2018	Greenbrier County Airport Authority	6/8/2018		$ 758,000	$ 3,678,409	$ 4,436,409	Install Airport Beacons, Rehabilitate Apron
WY	Casper	Casper/Natrona County International	CPR	3-56-0004-058-2018	County of Natrona Board of Trustees	6/8/2018		$ 1,225,172	$ 1,435,000	$ 2,660,172	Rehabilitate Taxiway
WY	Cody	Yellowstone Regional	COD	3-56-0006-039-2018	City of Cody	6/8/2018		$ 398,745	$ -	$ 398,745	Update Airport Master Plan Study
WY	Cody	Yellowstone Regional	COD	3-56-0006-038-2018	City of Cody	6/8/2018		$ 1,297,681	$ -	$ 1,297,681	Expand Apron
WY	Dubois	Dubois Municipal	DUB	3-56-0010-019-2018	Town of Dubois	6/8/2018		$ 80,000	$ -	$ 80,000	Install Miscellaneous NAVAIDS, Rehabilitate Apron
WY	Fort Bridger	Fort Bridger	FBR	3-56-0042-013-2018	County of Uinta	6/8/2018		$ 565,048	$ -	$ 565,048	Rehabilitate Apron
WY	Laramie	Laramie Regional	LAR	3-56-0017-036-2018	Laramie Regional Airport	6/8/2018		$ 1,321,878	$ 3,128,122	$ 4,450,000	Rehabilitate Runway - 03/21, Rehabilitate Runway Lighting - 03/21
WY	Pinedale	Ralph Wenz Field	PNA	3-56-0021-021-2018	Town of Pinedale	6/8/2018		$ 181,773	$ -	$ 181,773	Rehabilitate Apron
WY	Rawlins	Rawlins Municipal/Harvey Field	RWL	3-56-0023-017-2018	City of Rawlins	6/8/2018		$ 302,653	$ -	$ 302,653	Update Airport Master Plan Study
WY	Riverton	Riverton Regional	RIW	3-56-0024-045-2018	City of Riverton	6/8/2018		$ 1,816,117	$ -	$ 1,816,117	Rehabilitate Apron
WY	Thermopolis	Hot Springs County	HSG	3-56-0043-010-2018	County of Hot Springs	6/8/2018		$ 150,000	$ -	$ 150,000	Improve Airport Drainage

401-3.4 Reclaimed asphalt pavement (RAP). [RAP shall not be used.] [Reclaimed asphalt shall consist of reclaimed asphalt pavement (RAP), coarse aggregate, fine aggregate, mineral filler, and asphalt. The RAP shall be of a consistent gradation and asphalt content and properties. When RAP is fed into the plant, the maximum RAP size shall not exceed one inch (25 mm). The reclaimed asphalt pavement mix shall be designed using procedures contained in the Asphalt Institute MS-2 Mix Design Manual, 7th Edition. The percentage of asphalt in the RAP shall be established for the mixture design according to ASTM D2172 using the appropriate dust correction procedure. The JMF shall meet the requirements of paragraph 401-3.3**. RAP shall only be used for shoulder surface course mixes and for any intermediate courses.** The amount of RAP shall be limited to [ ] percent. In addition to the requirements of paragraph 401-3.3, the JMF shall indicate the percent of reclaimed asphalt pavement and the percent and grade of new asphalt binder. For the PG graded asphalt binder selected in 401-2.3, adjust as follows:
a. For 0-20% RAP, there is no change in virgin asphalt binder content.
b. For >20 to 30% RAP, select asphalt binder one grade softer, i.e., PG 64-22 would soften to PG 58-28.
RAP containing Coal Tar shall not be used. Coal Tar surface treatments must be removed prior to recycling underlying asphalt material.

Recycled asphalt shingles (RAS) shall not be used.]
****

Engineer will determine if RAP is/is not allowed and make appropriate selection. RAP should not be used for surface mixes, except on shoulders. It can be used very effectively in lower layers or for shoulders. Engineer to specify the maximum percentage of reclaimed asphalt allowed in the mix. The amount of RAP shall be limited to 30%, as long as the resulting recycled mix meets all requirements that are specified for virgin mixtures. The Contractor may obtain the RAP from the job site or an existing source.